

BILLS OF QUANTITIES FOR SEVEN DWELLING HOUSES (5METRES BY 4

ITEM	QUANTITY	RATE (MK)
Iron sheets (8 feet) 32 gauge	140	2288
Ridges	28	1200
Planks (18 x4 x2)	49	3500
Planks (18 x3 x2)	63	2500
Door frame	28	3500
Doors (FLBB)	28	8,000
Window frames(6 glass)	14	3,500
Window frames (3 glass)	14	2,000
Window sashes	42	1,200
Cement	49	6,500
Bricks	24500	15
Sand -- 2 trips 3 tonne	14	15,000
Wire nail -- 5 inches (kg)	28	1,000
Wire nail -- 4 inches (kg)	14	1,000
Roofing nails (kg)	21	1,200
Gate latch locks	14	2,000
Glass(12x10)	126	350
Material transportation	7	25400
Labour charges	7	65000
TOTAL COST (MK)		
TOTAL COST (US\$)		

Note: US\$1.00 = MK560

METRES)

TOTAL COST (MK)

320,320
33,600
171,500
157,500
98,000
224,000
49,000
28,000
50,400
318,500
367,500
210,000
28,000
14,000
25,200
28,000
44,100
177,800
455,000
2,800,420
5,000