

BILLS OF QUANTITIES FOR SEVEN DWELLING HOUSES (5METRES BY 4 M

ITEM	QUANTITY	RATE (MK)
Iron sheets (8 feet) 32 gauge	140	3200
Ridges	28	1800
Planks (18 x4 x2)	49	4200
Planks (18 x3 x2)	63	3500
Door frame	28	5000
Doors (FLBB)	28	15,000
Window frames(6 glass)	14	4,000
Window frames (3 glass)	14	3,000
Window sashes	42	1,200
Cement	49	6,700
Bricks	24500	15
Sand -- 2 trips 3 tonne	14	15,000
Wire nail -- 5 inches (kg)	28	1,200
Wire nail -- 4 inches (kg)	14	1,200
Roofing nails (kg)	21	1,400
Gate latch locks	14	2,500
Glass(12x10)	126	500
Material transportation	7	45000
Labour charges	7	80000
TOTAL COST (MK)		
TOTAL COST (US\$)		

Note: US\$1.00 = MK718

METRES)

TOTAL COST (MK)

448,000
50,400
205,800
220,500
140,000
420,000
56,000
42,000
50,400
328,300
367,500
210,000
33,600
16,800
29,400
35,000
63,000
315,000
560,000
3,591,700
5,002