



Rocky Mountain
HARDSCAPES

Date: May 11, 2019

Proposal

Camp Rotary
Neihart, MT

Install sand volleyball court as follows:

- Overall court dimensions to be 42' wide by 72' long
- Install 2 courses of 4 x 6 treated timbers to create a court surround
- Install 100 yards of topsoil to level the court area
- Install 30 yards of ¾" fractured gravel for drainage
- Install geotextile fabric above drainage rock
- Install 74 yards of washed sand \$11,000

Install 2 treated 6 x 6 posts for volleyball standards

- Set posts in concrete below grade for stability
- Provide volleyball hardware including net, cables & winch system \$1,190

Total \$12,190

*** Bid assumes the ability to get across the bridge with our equipment and materials. (At least 15 ton bridge limit)**

Terms: 50% down and 50% upon completion

Rocky Mountain Hardscapes is an ICPI certified paver installer, BTS certified paver installer & NCMA certified segmental retaining wall installer
MT State Contractor 157453

915 Crescent Drive • Great Falls, MT 59404 • Office 761-2625 • Mobile 868-7552